

ESTIMATE
Construction of Basket Ball Court at Tezpur College, Tezpur
Dist. Sonitpur, Assam.

Sl. No.	Particulars Description of the Items	Unit	Quant	Rate	Amount
1	Cleaning of grass and removal of rubbish upto a distance of 30.00 M outside the periphery of the area as per technical specification clause 201. Qty:- $70.00 \times 45.00 = 3,150.00\text{Sqm}$ $= 0.315$ hectre	Hectre			
2	Item no. 30.1 Construction of Sub-grade and earthen shoulders with approved materials obtained from borrow pits, with all lifts and leads, transporting to site, spreading, grading to required slope and compacting to meet requirement of table 300-2(including compaction of earth)(including cost of testing of materials at site and laboratory as directed complete) a) From Private land Qty: $50.00 \times 30.00 \times 0.40 = 600.00$	CuM			
3	Cl. 30.2. : Construction of Granular sub-base by providing close graded material, spreading in uniform layers with motor grader on prepared surface, mixing by mix in place method with rotovator at OMC, and compacting with vibratory roller to achieve the desired density, complete as per Cl. 401 of MORTH specifications (with a initial lead of 5.00Km) (including cost of testing of materials at site and laboratory as directed complete) c) Using grading II materials Qty: $1 \times 34.50 \times 21.50 \times 0.20 = 148.35$	CuM			
4	Water Bound Macadam : Providing laying, spreading compacting stone aggregates of specific sizes to water bound macadam specification including				

